

BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to :

Original / Duplicate
Item No.

Name of work: Estimate for Desilting and Removing and Resetting of BS Slab, Debris Clearing and Maintenance of Culverts in Ward No. 05 Surrounding Area Byatarayanapura Sub Division

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	91.00	KSRB 14.10.1 : Flooring with 25mm to 40mm thick polished tandur blue stone slabs using mortar 1:6, 25mm thick over existing cement concrete bed or top of roof laid to line and level and jointed with cement slurry mixed with pigment to match the shade of the slab, including cost of materials, labour, curing, polishing complete as per specifications. Page No. 109/ Item No. 14.15 / PWD SR 2011-12	Sqm	810.22	Rupees Eight Hundred Ten and Twenty Two Paise Only
2	7.06	KSRB 14.14-5: providing Ceramic tiles of approved make, shade and size for flooring, treads of steps and landings laid on a bed of 12mm thick, cement mortar 1:3 mix, flush pointing with white cement using colour pigment, including cost of materials, labour, curing, complete as per specifications. Page No. 113/ Item No. 14.36 / PWD SR 2011-12	Sqm	800.13	Rupees Eight Hundred and Thirteen Paise Only
3	29.26	KSRB 14.17.2: Providing skirting, dado, rises of steps with Colour glazed tiles 6mm thick on 10mm thick cement plaster 1:3 and jointed with white cement slurry over rough plaster surface (excluding cost of rough plastered surface white should be measured and paid separately) using glazed tiles of approved make and size of materials, labour, complete as per specifications. Specification No. KBS 14.17. Page No. 114/ Item No. 14.41 / PWD SR 2011-12	Sqm	900.45	Rupees Nine Hundred and Forty Five Paise Only
4	4.39	"SOLID PANEL PVC DOOR SHUTTER" Providing & fixing 30mm thick factory made rigid foam Panelled Door Shutters made from M.S. tube of 19 gauge thickness, size 19x19mm from styles and 15x15mm for top & bottom rails, covered with heat moulded PVC 'C' channel of 5mm thick sheet & 30 x 50 mm wide to form styles & 5mm thick & 75mm wide PVC Sheets for top rail, lock rail & bottom rail on either side & 5mm thick 20mm wide PVC sheet as gap insert for top rail & bottom rail, Panelling of 5mm thick PVC sheet fitted in the M.S. Frame, Sealed to the styles & rails with 5x30mm PVC sheet beading on either side & joined together with solvent cement adhesive etc.; Complete as per manufacturers specification & direction of Engineer-in charge fixed to frames with 3 nos of 75m.m. Aluminium hinges. Page No. 62/ Item No. 9.83/ PWD SR 2011-12	Sqm	2007.64	Rupees Two Thousand Seven and Sixty Four Paise Only
5	208.99	KSRB 15-16 : Providing and finishing external walls in two coats with waterproof cement paint of approved brand and shade to given an even shade after thoroughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications. Page No. 124/ Item No. 15.53 / PWD SR 2011-12	Sqm	47.70	Rupees Forty Seven and Seventy Paise Only

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
6	1192.20	KSRB 2-1.1: Earth work in surface excavation in ordinary soil for leveling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe line and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed as per specifications, Specification No KBS 2.1(a) / 2.3.1, P. No. 5/ Item No. 2.1/ PWD SR 2015-16	cum	159.84	Rupees One Hundred Fifty Nine and Eighty Four Paise Only
7	76.17	KSRB 2-2.1 : earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, in Hard soil not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods complete as per specifications, specification, No, KBS 2.1(a) / 2.3.5, No. 5/ Item No. 2.4/ PWD SR 2014-15	Cum	264.60	Rupees Two Hundred Sixty Four and Sixty Paise Only
8	3405.60	Removing B.S Slab of Drain and stacking Page No. 25/ Item No. 5.32/ PWD SR 2015-16	Sqm	63.72	Rupees Sixty Three and Seventy Two Paise Only
9	3405.60	Refixing stone slabs of drains and pointing in C.M (1:3) Page No. 25/ Item No. 5.33/ PWD SR 2015-16	Sqm	78.84	Rupees Seventy Eight and Eighty Four Paise Only
10	851.40	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar(1:6) including fixing curing etc, complete - do- 7.5 cms thick Page No. 28/ Item No. 5.31.1/ PWD SR 2015-16	Sqm	663.12	Rupees Six Hundred Sixty Three and Twelve Paise Only
11	10.88	KSRB-4-1.3 : Providing and laying in position plain cement concrete of mix M 1:4:8 with OPC cement at 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2, No. 12/ Item No. 4.3/ PWD SR 2014-15	Cum	4847.04	Rupees Four Thousand Eight Hundred Forty Seven and Four Paise Only
12	20.09	KSRB 5.2.3 Providing and constructing granite / trap / basalt Size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5.1.13 Page No. 23/ Item No. 5.6/ PWD SR 2014-15	cum	3836.16	Rupees Three Thousand Eight Hundred Thirty Six and Sixteen Paise Only
13	16.74	KSRB 5.3-3 Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5-1.13 Page No. 23/ Item No. 5.9/ PWD SR 2014-15	Sqm	4542.48	Rupees Four Thousand Five Hundred Forty Two and Forty Eight Paise Only
14	43.99	KSRB 4-6.7 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for sides and soffits of beams, beam haunchings, cantilever girders, bressumers and lintels not exceeding 1 m in depth including cost of all materials, labour complete as per specifications. Specification NO KBS 4.6.2 Page No. 16/ Item No. 4.34/ PWD SR 2014-15	Sqm	260.28	Rupees Two Hundred Sixty and Twenty Eight Paise Only

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
15	5.95	KSRB 4-1.7 : : Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 20mm and down size graded granite metal coarse aggregates @0.84cum and fine aggregates @0.56cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1.4.2/P No. 13/ Item No. 4.7/ PWD SR 2014-15	cum	5287.68	Rupees Five Thousand Two Hundred Eighty Seven and Sixty Eight Paise Only
16	37.20	KSRB 15.1.3: Providing FLush pointing to coursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications. Page No. 109/ Item No. 15.1/ PWD SR 2014-15	Sqm	91.80	Rupees Ninety One and Eighty Paise Only
17	14.12	KSRB 4.2.2 : Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum with superplastesisre @ 3lts conforming to IS9103-1999Reffirmed machine mixed exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, walls(any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour HOM of machinery, curing, complete as per specifications. Specification. No. KBS 4.1.4.6, No. KBS 4.1.4.6, No. 13/ Item No. 4.11/ PWD SR 2014-15	Cum	6065.28	Rupees Six Thousand Sixty Five and Twenty Eight Paise Only
18	0.99	KSRB 4.9.2:providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications.Specification No. KBS 4.6.3 Page No. 17/ Item No. 4.46.2/ PWD SR 2014-15	Qtl	78351.84	Rupees Seventy Eight Thousand Three Hundred Fifty One and Eighty Four Paise Only
19	1268.37	Lead for Disposal of Debris shall be payable at carage rates by Mechanical means including loading and unloading. From 0.00 to 2.00 Km (Page No.123,	Cum	62.20	Rupees Sixty Two and Twenty Paise Only



 Executive Engineer,
 Byatarayanapura Division
 BBMP, Bangalore - 92

26/12/15

Note:

- Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)
- Unit rates and prices shall be quoted by the Tender in Indian rupees.
- Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a))
- Where there is a discrepancy between the unit rate and the line item total resulting from multiplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))

ಕರಡು ಬೆಂದರ್ ಪಡೆಯಲ್ಪಟ್ಟು
 ಶಿಫ್ಟಿಪಡೆಗಳ ಸಂಖ್ಯೆ.....()
 ಶಿಫ್ಟಿಪಡೆ ಮಾಡಿ/ಇಲ್ಲದ
 ಅನುಮೋದನೆ ನೀಡಿಲಾಗಿರುತ್ತದೆ


 Page 3 of 3